

AD-A109 971

TIPPETTS-ABBETT-MCCARTHY-STRATTON NEW YORK  
NATIONAL DAM SAFETY PROGRAM. LAKE MAHOPAC DAM (INVENTORY NUMBER--ETC(U)  
SEP 81 E O'BRIEN

F/G 13/13


DACW51-81-C-0008

NL

UNCLASSIFIED

1 OF 1  
ALL INFORMATION CONTAINED  
HEREIN IS UNCLASSIFIED

END  
DATE  
FILMED  
03-82  
DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

## REPORT DOCUMENTATION PAGE

READ INSTRUCTIONS  
BEFORE COMPLETING FORM

1. REPORT NUMBER

2. GOVT ACCESSION NO.

3. RECIPIENT'S CATALOG NUMBER

4. TITLE (and Subtitle)

Phase I Inspection Report

Lake Mahopac Dam

Lower Hudson River Basin, Putnam County, NY

Inventory No. 1329

7. AUTHOR(s)

EUGENE O'Brien

9. PERFORMING ORGANIZATION NAME AND ADDRESS

Tippett-Abbott-McCarthy-Stratton

The TAMS Building

555 Third Avenue New York, New York 10017

10. CONTROLLING OFFICE NAME AND ADDRESS

Department of the Army

26 Federal Plaza New York District, CoE

New York, New York 10287

11. MONITORING AGENCY NAME &amp; ADDRESS (if different from Controlling Office)

Department of the Army

26 Federal Plaza New York District, CoE

New York, NY 10287

8. CONTRACT OR GRANT NUMBER(s)

DACW51-81-C-0008

10. PROGRAM ELEMENT, PROJECT, TASK  
AREA & WORK UNIT NUMBERS

12. REPORT DATE

14 August 1981

13. NUMBER OF PAGES

15. SECURITY CLASS. (of this report)

UNCLASSIFIED

15a. DECLASSIFICATION/DOWNGRADING  
SCHEDULE

16. DISTRIBUTION STATEMENT (of this Report)

Approved for public release; Distribution unlimited.

17. DISTRIBUTION STATEMENT (of the Abstract entered in Block 20, if different from Report)

18. SUPPLEMENTARY NOTES

19. KEY WORDS (Continue on reverse side if necessary and identify by block number)

Dam Safety

National Dam Safety Program

Visual Inspection

Hydrology, Structural Stability

Lake Mahopac Dam

Putnam County

Lower Hudson River Basin

20. ABSTRACT (Continue on reverse side if necessary and identify by block number)

This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.


The examination of documents and the visual inspection of Lake Mahopac Dam and its appurtenant structures did not reveal conditions which constitute an immediate hazard to human life and property.

AD A109971

DTIC FILE COPY

Using Corps of Engineers screening criteria, it has been determined that the dam would be overtopped for all storms exceeding approximately 56 percent of Probable Maximum Flood (PMF). The maximum spillway discharge capacity is 7.9 percent of the PMF peak outflow. The spillway is, therefore adjudged as "inadequate".

1900 217 210



**LOWER HUDSON RIVER BASIN**

**LAKE MAHOPAC DAM**

**PUTNAM COUNTY, NEW YORK  
INVENTORY NO. N.Y. 1329**

**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**

DTIC  
JAN 21 1982  
H



**NEW YORK DISTRICT CORPS OF ENGINEERS**

**SEPTEMBER 1981**

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84

10



**II**

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
LAKE MAHOPAC DAM  
I.D. NO. N.Y. 1329  
D.E.C. NO. 213D-4462  
LOWER HUDSON RIVER BASIN  
PUTNAM COUNTY, N.Y.

CONTENTS

	<u>Page No.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1. PROJECT INFORMATION	1
1.1 GENERAL	1
a. Authority	1
b. Purpose of Inspection	1
1.2 DESCRIPTION OF THE PROJECT	1
a. Description of Dam and Appurtenant Structures	1
b. Location	2
c. Size Classification	2
d. Hazard Classification	2
e. Ownership	2
f. Purpose of Dam	2
g. Design and Construction History	2
h. Normal Operating Procedures	3
1.3 PERTINENT DATA	
a. Drainage Area	3
b. Discharge at Damsite	3
c. Elevation	3
d. Reservoir	3
e. Storage	3
f. Dam	3
g. Spillway	3
h. Reservoir Drain	3
2. ENGINEERING DATA	4
2.1 GEOLOGY	4
2.2 SUBSURFACE INVESTIGATIONS	4



	<u>Page No.</u>
2.3 DAM AND APPURTENANT STRUCTURES	4
2.4 CONSTRUCTION RECORDS	4
2.5 OPERATION RECORDS	4
2.6 EVALUATION DATA	4
3 VISUAL OBSERVATION	5
3.1 FINDINGS	5
a. General	5
b. Dam	5
c. Spillway-Reservoir Drain	5
d. Abutments	5
e. Downstream Channel	6
f. Reservoir Area	6
3.2 EVALUATION OF OBSERVATIONS	6
4 OPERATION AND MAINTENANCE PROCEDURES	7
4.1 PROCEDURES	7
4.2 MAINTENANCE OF THE DAM	7
4.3 MAINTENANCE OF OPERATING EQUIPMENT	7
4.4 WARNING SYSTEM IN EFFECT	7
4.5 EVALUATION	7
5 HYDROLOGIC/HYDRAULIC	8
5.1 DRAINAGE AREA CHARACTERISTICS	8
5.2 ANALYSIS CRITERIA	8
5.3 SPILLWAY CAPACITY	8
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	9

		Page No.
6	STRUCTURAL STABILITY	10
6.1	EVALUATION OF STRUCTURAL STABILITY	10
	a. Visual Observation	10
	b. Design and Construction Data	10
	c. Operating Records	10
	d. Post Construction Changes	10
	e. Seismic Stability	10
6.2	STRUCTURAL STABILITY ANALYSIS	10
7	ASSESSMENT/RECOMMENDATIONS	11
7.1	ASSESSMENT	11
	a. Safety	11
	b. Adequacy of Information	11
	c. Need for Additional Investigations	11
	d. Urgency	11
7.2	RECOMMENDED MEASURES	11

#### APPENDICES

- A. DRAWINGS
  - a. Vicinity Map
  - b. Topographic Map
  - c. Mahopac Lake Dam-Plan
  - d. Mahopac Lake Dam-Spillway  
Reservoir Drain Structure, Plan
  - e. Mahopac Lake Dam-Spillway  
Reservoir Drain Structure, Section
- B. PHOTOGRAPHS
- C. VISUAL INSPECTION CHECKLIST
- D. HYDROLOGIC DATA AND COMPUTATIONS
- E. REFERENCES

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

NAME OF DAM: Lake Mahopac Dam, N.Y. 1329  
STATE LOCATED: New York  
COUNTY LOCATED: Putnam  
STREAM: Tributary of Muscoot River  
BASIN: Lower Hudson River  
DATE OF INSPECTION 6 May 1981

ASSESSMENT

→ The examination of documents and the visual inspection of Lake Mahopac Dam and its appurtenant structures did not reveal conditions which constitute an immediate hazard to human life and property.

Using Corps of Engineers screening criteria, it has been determined that the dam would be overtopped for all storms exceeding approximately 56 percent of Probable Maximum Flood (PMF). The maximum spillway discharge capacity is 7.9 percent of the PMF peak outflow. The spillway is, therefore adjudged as "inadequate".

The following remedial measures should be performed within 12 months from notification:

(1) Missing portions of the upstream stone masonry wall should be repaired.

(2) Brush and shrubbery should be removed from the embankment, spillway-reservoir drain structure and downstream channel. Provide a program of periodic cutting and or mowing of the dam surfaces, spillway-reservoir drain structure and the downstream channel.

→ next page

cont  
(3) The collected debris at the spillway-reservoir drain structure and in the downstream channel should be removed and hauled away from the dam.

(4) A program of periodic inspections and maintenance of the dam and appurtenances should be provided, including yearly operation and lubrication of the reservoir drain and its control facilities. This information should be documented for future reference.

(5) An emergency action plan for the project should be developed.

*Eugene O'Brien*

Eugene O'Brien, P.E.  
New York No. 29823

Approved by:

*W. M. Smith, Jr.*

Col. W. M. Smith, Jr.  
New York District Engineer

Date:

*14 Aug 61*

*-V-*



1. OVERVIEW OF DAM.

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
LAKE MAHOPAC DAM  
I.D. NO. N.Y. 1329  
D.E.C. NO. 213D-4462  
LOWER HUDSON RIVER BASIN  
PUTNAM COUNTY, N.Y.

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers by Contract No. DACW 51-81-C-0008 dated 14 December 1980 in fulfillment of the requirements of the National Dam Inspection Act, Public Law 92-367, 8 August 1972.

b. Purpose of Inspection

The inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF THE PROJECT

a. Description of Dam and Appurtenant Structures

Lake Mahopac Dam consists of an earth embankment about 190 feet long and has a maximum height of about 9 feet. The width of the crest varies from 25 feet to 50 feet. The visible portion of the upstream face of the embankment is vertical and is retained by a 2 foot wide stone masonry wall. The downstream slope of the embankment, to the right of a spillway-reservoir drain structure, is vertical and protected by a 2 foot wide stone masonry wall; to the left of the spillway-reservoir drain structure it is 1 vertical to 4 horizontal near the crest and vertically retained by one of the stone masonry walls of the spillway-reservoir drain downstream channel.

A stone masonry/concrete structure, which serves as a spillway and a reservoir drain is located about 25 feet from the right abutment. The crest of the spillway is about 3 feet from the top of the dam and is 8 feet wide. Two foot wide stone masonry approach and downstream training walls flank the structure.

The reservoir drain is located at the bottom of the structure. The discharge through the reservoir drain is controlled by a sluice gate which can be operated from the top of the structure. The gate is about 12 feet downstream from the spillway crest. The discharges over the crest and through the reservoir drain flow over a sloping concrete apron, then into the downstream channel. The downstream channel is stone masonry lined, about 5 feet wide and 6 feet high. The channel invert forms the toe of the embankment. Its alignment makes a 120° bend about 100 feet from the spillway-reservoir drain structure; continues along Peeksville Road for 1500 feet where it joins the downstream channel of Kirk Lake.

b. Location

The dam is located on a tributary of Muscoot River and Hudson River; approximately 800 feet from the intersection of Peeksville Road and West Lake Blvd. in the Village of Mahopac Falls.

c. Size Classification

The dam is about 9 feet high and impounds approximately 1300 acre-feet. Therefore, the dam is in the "intermediate" size category (between 1000 acre-feet and 50,000 acre-feet).

d. Hazard Classification

The dam is classified as high hazard due to several homes, a highway and commercial properties located 0.25 miles downstream from the dam.

e. Ownership

Lake Mahopac is owned by the Town of Carmel. The person to contact is Town Supervisor, Town Hall, Town of Carmel, McAlpin Avenue, Mahopac, New York, 10541, Telephone No. (914) 628-1470. At present the town supervisor is Mr. Dean Barrett. The maintenance of the dam is the responsibility of the Highway Department of the Town.

f. Purpose of Dam

The impoundment provided by the dam is mainly for recreation. The lake also supplies water to developments around the lake.

g. Design and Construction History

Original design and construction records are not available. It is reported that the dam was designed and constructed in 1940. The names of the designer and the contractor are unknown.

h. Normal Operating Procedures

There are no normal operating procedures.

Lake level is maintained at the spillway crest in spring and summer. In fall the lake level is lowered by 1 to 1.5 feet to allow maintenance of docks and prevent damage to docks due to ice in winter.

1.3 PERTINENT DATA

a.	<u>Drainage Area</u> , Square Miles	2.7
b.	<u>Discharge at Damsite</u> , cfs	
	Ungated spillway capacity at El 660	108.8
c.	<u>Elevation</u> (Feet above MSL)	
	Top of Dam	660.00
	Spillway Crest	657.00
	Reservoir Drain (at Sluice Gate)	653.7
d.	<u>Reservoir</u>	
	Length of Normal Pool (Miles)	0.8
	Surface Area at El 657 (Acres)	608
	Surface Area at El 660 (Acres)	625
e.	<u>Storage</u> (Acre-Feet)	
	Top of Spillway Crest (El 657)	1300
	Top of Dam (El 660.0)	3080
f.	<u>Dam</u>	
	Type	Earth Embankment
	Length (Feet)	190
	Height (Feet)	9
	Crest Width (Feet)	Varies from 25 to 50 feet
	Side Slopes:	
	Upstream	Vertical, Stone masonry wall
	Downstream, Right of Spill- way-Reservoir Drain Structure	Vertical, Stone masonry wall
	Downstream, Left of Spill- way-Reservoir Drain Structure	1 (V):4 (H) and vertical stone masonry wall
g.	<u>Spillway</u>	
	Type	Sharp-crested, Stone Masonry-concrete
	Length	8 ft
	Crest Elevation	657.0
h.	<u>Reservoir Drain</u>	
	Type	15-inch diameter sluice way
	Elevation (Invert)	Intake 653.7



## SECTION 2 - ENGINEERING DATA

### 2.1 GEOLOGY

The records of the owner contain no data on site geology. However, there is data available in the literature on the general geology of the area. Mahopac Lake Dam is located in the Hudson Highlands section of the New England Uplands physiographic province. The province is characterized by a low, but rugged mountain range consisting primarily of igneous and metamorphic rock. The rock underlying the area of the dam is Precambrian biotite-quartz-plagioclase paragneiss with subordinate biotite granitic gneiss, amphibolite and calcilicate rock.

### 2.2 SUBSURFACE INVESTIGATIONS

There are no records of subsurface investigations available. It is known that the surficial soils in the vicinity of the dam and reservoir are coarse grained glacial till material.

### 2.3 DAM AND APPURTENANT STRUCTURES

There are no design data, construction drawings or design memoranda available for the project features.

### 2.4 CONSTRUCTION RECORDS

There are no records of the original construction of the dam available. The name(s) of the contractor is (are) unknown.

### 2.5 OPERATION RECORDS

There are no records of operation of the dam. The reservoir drain sluice gate is reportedly operated during fall to lower the lake level by 1 foot to 1.5 feet so that maintenance of the docks may be carried out and to prevent damage to the docks by ice. There is no formal operation and maintenance manual for the project. No records of reservoir levels and rainfall are kept.

### 2.6 EVALUATION DATA

Information was made available by the New York State Department of Environmental Conservation and the Town of Carmel, New York.

The information obtained from the available data, personal interviews and the visual inspection are considered adequate for this Phase I inspection and evaluation.

## SECTION 3 - VISUAL OBSERVATION

### 3.1 FINDINGS

#### a. General

The visual observation of the Mahopac Dam was made on 6 May 1981. The weather was sunny with the temperature ranging between 60 and 70° F. At the time of inspection, the reservoir level was about El 657.2, 2 inches above the crest of the spillway-reservoir drain structure. The reservoir drain was closed.

#### b. Dam

The dam, which consists of earth embankment appears to be in generally good condition. There are no visible signs of distress or movement. The horizontal and vertical alignment of the crest are also good.

The visible portion of the upstream slope which is protected by a vertical stone masonry wall, appears to be in good condition except in the vicinity of the left abutment, where about 50 feet of the wall is missing. There is minor vegetation growing through the wall joints particularly near the spillway.

The downstream slopes as well as the stone masonry wall of the channel appear to be in good condition except for minor vegetation such as bushes and overgrown grass. The slope does not exhibit any erosion, sloughing or signs of trespassing. There are no signs of seepage at the downstream toe.

#### c. Spillway-Reservoir Drain

The spillway and reservoir drain which are located about 25 feet from the left abutment are part of a stone masonry-concrete structure. The exposed spillway portion of the structure and the downstream concrete apron appear to be in good condition except for debris collected at and inside the structure.

The reservoir drain and the control are in operating condition.

A detailed sketch showing the configuration of the spillway-reservoir drain structure as was determined from field measurements is given in Plates 4 and 5.

#### d. Abutments

There are no signs of seepage or other unusual conditions at both abutments.

e. Downstream Channel

The channel downstream of the spillway-reservoir drain structure is stone masonry lined rectangular in section and appears to be in generally good condition except for minor vegetation growing through the joints and collected debris.

f. Reservoir Area

In the vicinity of the dam there is no evidence of sloughing, potentially unstable slopes or other unusual conditions which would adversely affect the dam. No evidence of excessive sedimentation was observed. The lake water was relatively clean.

3.2 EVALUATION OF OBSERVATIONS

Visual observations made during the course of the inspection did not reveal serious problems which would adversely affect the adequacy of the dam and the appurtenant facilities. The following summarizes the encountered problem areas, in order of importance with the recommended remedial action:

1. The missing portion of the upstream stone masonry wall should be repaired.

2. The brush and shrubs should be removed from the embankment, spillway-reservoir drain structure and downstream channel. A program of periodic cutting and or mowing of the dam surfaces, spillway-reservoir drain structure and the downstream channel should be provided.

3. The collected debris at the spillway-reservoir drain structure and in the downstream channel should be removed and hauled away from the dam.

4. An emergency action plan for the project should be developed.

## SECTION 4 - OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

There are no operating procedures for regulating the discharges. The reservoir drain sluice gate is kept closed during the spring and summer so that the lake level is maintained at the spillway crest. In fall the lake level is maintained 1 to 1.5 feet below the spillway crest by discharging through the reservoir drain (gates kept open). It is reported that lowering the lake is done to allow for dock maintenance and to prevent ice damage to docks in the winter.

### 4.2 MAINTENANCE OF THE DAM

There is no operating and maintenance manual for the dam. There is no regular maintenance done at the dam, but is done as needed. The presence of the debris in the spillway and discharge channel, overgrown bushes and shrubs and trees is considered unacceptable.

### 4.3 MAINTENANCE OF OPERATING EQUIPMENT

There is no regular maintenance of the sluice gate of the reservoir drain. During the inspection the sluice gate was operated and appears to be in good condition except for minor rusting of the stem. The operating mechanism for the gate is kept at the Highway Department, Town of Carmel.

### 4.4 WARNING SYSTEM IN EFFECT

There is no warning system in effect or in preparation.

### 4.5 EVALUATION

The operation and maintenance of Lake Mahopac Dam is considered inadequate in the following areas:

1. Maintenance of the upstream stone masonry wall.
2. Control of vegetation on the embankment and in the spillway-reservoir drain structure and its channel.
3. Debris in and at the spillway-reservoir drain structure.

## SECTION 5 - HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

Lake Mahopac is located in Carmel Township, Putnam County, New York (Hydrologic Unit Code No. 02030101), and is the headwater of the Muscoot River, with a drainage area of 2.7 square miles. The lake surface area at elevation 657 is 0.95 square miles or 35 percent of the drainage area. The basin consists of a northern sub-area of 0.94 square miles, relatively undeveloped with some surface storage in Wixon Pond and a small wet-land area. The urbanized southern sub-area has little storage in its 0.83 square miles and no defined river channels. The basin is extremely narrow on the eastern and western sides of the lake.

### 5.2 ANALYSIS CRITERIA

The analysis of the adequacy of the spillway was performed by developing a design flood using the unit hydrograph method and the Probable Maximum Precipitation (PMP). The all season 200 square mile 24 hour PMP for the Lake Mahopac basin of 22 inches was obtained from Hydro-meteorological Report No. 33, and distributed according to Standard Project Flood Determination, EM 1110-2-1411, Army Corps of Engineers.

The unit hydrograph for each sub-area was computed using Snyder's method with coefficients of 2 and 0.625 for  $C_T$  and  $C_p$ , respectively. Rainfall loss parameters of 1.0 inch initial loss and 0.1 inch per hour constant loss were selected as representative for the PMP event. In accordance with the recommended guidelines for Safety Inspection of Dams, the adequacy of the spillway was analyzed using the Probable Maximum Flood (PMF). A multi-plan analysis was performed for 50%, 75% and 100% PMF.

### 5.3 SPILLWAY CAPACITY

The maximum discharge of the unconventional structured spillway, was computed to be 108.8 cfs with the lake surface at El 660, and the sluice gate closed. A low coefficient of discharge was selected in order to represent the obstruction to flow caused by the structure built in the spillway channel.

#### 5.4 RESERVOIR CAPACITY

The normal capacity of the reservoir is listed as 1300 acre-feet. The computed surcharge storage between spillway crest (El 657) and the top of the dam (El 660) is 1780 acre-feet, which is equivalent to approximately 12.4 inches of runoff over the entire drainage area.

#### 5.5 FLOODS OF RECORD

There are no records of floods or maximum reservoir elevations at the dam.

#### 5.6 OVERTOPPING POTENTIAL

The potential of the dam being overtopped was investigated on the basis of the spillway discharge capacity and the available surcharge storage to meet the selected design flood inflows.

The HEC-1DB analysis was performed assuming that the water surface of the lake was at spillway crest elevation at the start of the flood event. The basin was divided into two sub-areas and the combined hydrographs routed through the lake.

The results of the multi-ratio analysis are as follows:

<u>RATIO OF PMF</u>	<u>PEAK INFLOW</u>	<u>PEAK OUTFLOW</u>	<u>OVERTOPPING</u>
1.00	7797 cfs	1372 cfs	1.57 ft.
0.75	5848 cfs	540 cfs	0.74 ft.
0.50	3899 cfs	99 cfs	0.00 ft.

The dam would be overtopped by all floods exceeding 56 percent of the PMF. The maximum spillway discharge capacity is 7.9 percent of the peak PMF outflow.

#### 5.7 EVALUATION

The dam does not have sufficient capacity to pass PMF, however, it has capacity to pass one-half PMF. Using the Corps of Engineers screening criteria, the spillway is therefore assessed as being "inadequate".

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observation

Visual observations did not indicate either existing or potential problems with the dam and spillway-reservoir drain structure. The observed missing wall at the upstream face is not detrimental to the dam's stability or safety at the present time, however, condition should be repaired before it worsens.

#### b. Design and Construction Data

There exists no design computations or other data regarding the structural stability of the dam or spillway-reservoir drain structure.

#### c. Operating Records

There are no available records of the reservoir elevations and gate operations. No major operational problems which would affect the stability of the dam were reported.

#### d. Post Construction Changes

There are no records of post construction changes available.

#### e. Seismic Stability

According to the recommended Corps of Engineers guidelines, the dam is located in Seismic Zone No. 1. However, based on past earthquake history the New York State Geological Survey considers the site to be in Zone 2. Based on this assessment the dam is considered in the Seismic Zone 2.

### 6.2 STRUCTURAL STABILITY ANALYSIS

Analyses to determine the stability of the spillway-reservoir drain structure to withstand sliding or overturning were not performed. Considering the relatively small external loadings acting upon the relatively large, heavy concrete structure, it has been concluded on engineering judgment that the stability criteria (overturning and sliding) as set forth by U.S. Army Engineering Regulations ER 1110-2-106 Appendix B, will be met for all required loading cases.

## SECTION 7 - ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

Examination of the available documents and the visual inspection of Lake Mahopac Dam did not reveal any conditions which constitute an immediate hazard to life or property.

Using the Corps of Engineers screening criteria for examination of spillway adequacy, it has been determined that the dam would be overtopped for all storms exceeding approximately 56 percent of Probable Maximum Flood (PMF). The maximum spillway discharge capacity is 7.9 percent of the PMF peak outflow. The spillway is, therefore adjudged as "inadequate".

#### b. Adequacy of Information

This report and its conclusions are based on the visual inspection, interviews and hydrologic/hydraulic studies. This information and data are adequate for a Phase I inspection.

#### c. Need for Additional Information

No additional investigations are required for the project.

#### d. Urgency

All remedial actions described below should be completed within one year of notification to the owner.

### 7.2 RECOMMENDED MEASURES

The recommended measures are as follows:

1. The missing portion of the upstream stone masonry wall should be repaired.

2. Brush and shrubs should be removed from the embankment, spillway-reservoir drain structure and downstream channel. A program of periodic cutting and or mowing of the dam surfaces, spillway-reservoir drain structure and the downstream channel should be provided.

3. The collected debris at the spillway-reservoir drain structure and in the downstream channel should be removed and hauled away from the dam.





4. A program of periodic inspections and maintenance of the dam and appurtenances including yearly operation and lubrication of the reservoir drain and its control facilities should be provided. This information should be documented for future reference.

5. An emergency action plan for the project should be developed.


DRAWINGS

APPENDIX A



VICINITY MAP  
LAKE MAHOPAC DAM

OSCAWANA LAKE, N.Y. QUAD  
 LAKE CARMEL, N.Y. QUAD  
 CROTON FALLS, N.Y. QUAD  
 MOHEGAN LAKE, N.Y. QUAD



SCALE 1:24:000

TOPOGRAPHIC MAP  
 LAKE MAHOPAC DAM

NOTE  
 1. Drawing based on rough field measurement  
 2. Length of dam about 190 ft.

Lake Mahopac

Spillway-Reservoir  
 Drain structure

UPSTREAM  
 STONE MASONRY  
 WALL

Embankment


Embankment/abutment  
 contact

Stone Masonry  
 walls

Downstream Channel


PLAN  
 Scale: NTS

PLATE NO. 3.



**NOTES**


1. For note see Plate No. 3
2. For Section AA see Plate No. 5



SPILLWAY-RESERVOIR DRAIN STRUCTURE

PLAN  
SCALE: NTS

Plate No 4



SECTION AA  
SCALE: NTS

Plate No. 5


PHOTOGRAPHS

APPENDIX B




DRAWINGS

APPENDIX A



VICINITY MAP  
LAKE MAHOPAC DAM

OSCAWANA LAKE. N.Y. QUAD  
 LAKE CARMEL, N.Y. QUAD  
 CROTON FALLS, N.Y. QUAD  
 MOHEGAN LAKE, N.Y. QUAD



SCALE 1:24:000

TOPOGRAPHIC MAP  
 LAKE MAHOPAC DAM

NOTE  
1. Drawing based on rough field measurement.  
2. Length of dam about 190 ft.

Lake Mahopac

Spillway-Reservoir  
Drain structure

UPSTREAM  
STONE MASONRY  
Wall

Embankment


Embankment/abutment  
Contact

Stone Masonry  
Walls

Downstream Channel


PLAN  
Scale: NTS

PLATE NO. 3.



**NOTES**


1. For note see Plate No. 3
2. For Section AA see Plate No. 5



SPILLWAY-RESERVOIR DRAIN STRUCTURE

PLAN  
SCALE: NTS

Plate No 4



SECTION AA  
SCALE: NTS

Plate No. 5

PHOTOGRAPHS

APPENDIX B



2. UPSTREAM VIEW OF DAM. (NOTE: Floating Debris in Reservoir)




3. UPSTREAM VIEW AT SPILLWAY-RESERVOIR DRAIN STRUCTURE.





4. VIEW OF CREST FROM SPILLWAY-RESERVOIR  
DRAIN STRUCTURE LOOKING LEFT. (NOTE: Trees)



5. VIEW OF CREST LOOKING RIGHT. PHOTOGRAPH  
TAKEN ABOUT 70 FT FROM LEFT ABUTMENT/DAM  
CONTACT.



6. VIEW OF SPILLWAY-RESERVOIR DRAIN STRUCTURE  
SILL. (NOTE: Collected Debris)



7. VIEW OF SPILLWAY-RESERVOIR DRAIN STRUCTURE  
AT DRAIN OUTLET. (NOTE: Collected Debris)



8. VIEW OF DOWNSTREAM FACE OF SPILLWAY-  
RESERVOIR DRAIN STRUCTURE. (NOTE: Vege-  
tation and Collected Debris)



9. VIEW OF UPSTREAM FACE. (NOTE: Upstream  
Stone Wall Condition)



10. VIEW OF DOWNSTREAM CHANNEL - LOOKING RIGHT.



11. VIEW OF DOWNSTREAM CHANNEL - LOOKING LEFT.

VISUAL INSPECTION CHECKLIST

APPENDIX C

VISUAL INSPECTION CHECKLIST

1 Basic Data

a. General

Name of Dam LAKE MAHOPAC  
Fed. I.D. # N.Y. 1329 DEC Dam No. 213 D-4462  
River Basin HUDSON RIVER BASIN  
Location: Town MAHOPAC VILLAGE County PUTNAM  
Stream Name MUSCOOT RIVER  
Tributary of HUDSON RIVER  
Latitude (N) 41° 22.5° Longitude (W) 73 -45.3°  
Type of Dam EARTH  
Hazard Category HIGH (1)  
Date(s) of Inspection MAY 6, 81  
Weather Conditions Partly Cloudy; 60-70° F.  
Reservoir Level at Time of Inspection El. 657.2

b. Inspection Personnel HARVEY FELDMAN & JYOTINDRA PATEL

c. Persons Contacted (Including Address & Phone No.)  
MR. DEAN BARRETT, TOWN SUPERVISOR  
TOWN HALL, TOWN OF CARMEL  
Mc ALPIN AV.  
MAHOPAC NY 10541

d. History:

Date Constructed 1940 \* Date(s) Reconstructed —  
\* reported  
Designer Unknown  
Constructed By Unknown  
Owner TOWN OF CARMEL (Address as above)

## Embankment

### a. Characteristics

- (1) Embankment Material Earth fill; classification of earth fill unknown.
- (2) Cutoff Type Unknown
- (3) Impervious Core Unknown
- (4) Internal Drainage System Unknown
- (5) Miscellaneous None

### b. Crest

- (1) Vertical Alignment Good
- (2) Horizontal Alignment Good.
- (3) Surface Cracks none observed
- (4) Miscellaneous brushes and several large size trees; Several animal burrows

### c. Upstream Slope

- (1) Slope (Estimate) (V:H) VERTICAL - STONE WALL.
- (2) Undesirable Growth or Debris, Animal Burrows \_\_\_\_\_
- (3) Sloughing, Subsidence or Depressions Near left abutment about 30' ft of wall displaced and stones missing.

(4) Slope Protection — stone wall

(5) Surface Cracks or Movement at Toe Unobservable - below water level

d. Downstream Slope

(1) Slope (Estimate - V:H) Varies from Vertical to 1(V):4(H)

(2) Undesirable Growth or Debris, Animal Burrows Overgrown grass, brushes and animal burrows

(3) Sloughing, Subsidence or Depressions None observed.

(4) Surface Cracks or Movement at Toe None observed

(5) Seepage None observed

(6) External Drainage System (Ditches, Trenches; Blanket) None.  
however downstream spillway - low level outlet channel runs along the toe.

(7) Condition Around Outlet Structure

(8) Seepage Beyond Toe none observed.

e. Abutments - Embankment Contact

Both abutments - natural ground



(1) Erosion at Contact none observed

(2) Seepage Along Contact none observed.

3) Drainage System

a. Description of System Appears to be none

b. Condition of System                     

c. Discharge from Drainage System                     

d) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs,  
Piezometers, Etc.)                     

None

1 Reservoir

- a. Slopes Visible slopes in vicinity of Dam are in generally stable condition.
- b. Sedimentation \_\_\_\_\_
- c. Unusual Conditions Which Affect Dam none observed

2) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) Several homes, and Rt 6 downstream of Dam.
- b. Seepage, Unusual Growth (a) None observed. (b) none except brushes and trees.
- c. Evidence of Movement Beyond Toe of Dam none observed.
- d. Condition of Downstream Channel see spillway channel (7d.)

3) Spillway(s) (Including Discharge Conveyance Channel)

Spillway structure also has low level outlet.

- a. General The spillway structure also shall low level outlet (reservoir drain). Because of discharge flowing in the spillway the layout and details of the low level outlet could not be determine.
- b. Condition of Service Spillway Generally good except collected debris at and in spillway.

c. Condition of Auxiliary Spillway No Auxiliary spillway

d. Condition of Discharge Conveyance Channel Discharge channel (stone lined)  
is also for reservoir drain is in good condition except  
some brush growing through stone masonry  
joints and debris.

e. Reservoir Drain/Outlet \*

Type: Pipe \_\_\_\_\_ Conduit \_\_\_\_\_ Other Circular hole in Concrete  
Structure

Material: Concrete ☒ Metal \_\_\_\_\_ Other \_\_\_\_\_

Size: 15" \*\* Length \_\_\_\_\_

Invert Elevations: Entrance \_\_\_\_\_ Exit \_\_\_\_\_

Physical Condition (Describe): \_\_\_\_\_ Unobservable ☒

Material: \_\_\_\_\_ Under water

Joints: \_\_\_\_\_ Alignment \_\_\_\_\_

Structural Integrity: \_\_\_\_\_

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate ☒ Valve \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Operation: Operable ☒ Inoperable \_\_\_\_\_ Other \_\_\_\_\_

Present Condition (Describe): Gate was operated - appears  
to be in good condition.

\* Outlet of the reservoir drain is visible at the face of the spillway channel.

\*\* Approximate dimensions, since could not be  
determined because of discharge flowing.  
(measured at outlet end).

9) Structural

- a. Concrete Surfaces The spillway reservoir drain-structure concrete surface appears to be in relatively good condition
- b. Structural Cracking No structural cracking is visible at spillway reservoir drain-structure.
- c. Movement - Horizontal & Vertical Alignment (Settlement) None observed
- d. Junctions with Abutments or Embankments Junctions with embankment are in good condition
- e. Drains - Foundation, Joint, Face None visible
- f. Water Passages, Conduits, Sluices Not Accessible
- g. Seepage or Leakage None observed.

h. Joints - Construction, etc. None Visible

i. Foundation None Visible - Spillway structure  
founded on Glacial till.

j. Abutments None

k. Control Gates No structural control gates  
on spillway - Reservoir Drain Structure

l. Approach & Outlet Channels The outlet channel is  
stone masonry lined and in good condition. Minor  
vegetation growing through the joints and collected  
debris.

m. Energy Dissipators (Plunge Pool, etc.) None Applicable

n. Intake Structures None

o. Stability No calculations are available; Visual  
observation indicates there appears to be no problem.

p. Miscellaneous

10) Appurtenant Structures (Powerhouse, Lock, Gatehouse, Other)

a. Description and Condition

only spillway  
Reservoir drain structure - see  
previous comments.

I

HYDROLOGIC DATA AND COMPUTATIONS

APPENDIX D

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>660±</u>	<u>625</u>	<u>3080</u>
2) Design High Water (Max. Design Pool)	<u>—</u>	<u>—</u>	<u>—</u>
3) Auxiliary Spillway Crest	<u>NONE</u>	<u>—</u>	<u>—</u>
4) Pool Level with Flashboards	<u>—</u>	<u>—</u>	<u>—</u>
5) Service Spillway Crest	<u>657</u>	<u>608</u>	<u>1300</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>UNKNOWN</u>
2) Spillway @ Maximum High Water	<u>42</u>
3) Spillway @ Design High Water	<u>UNKNOWN</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>—</u>
5) Low Level Outlet (Reservoir drain)	<u>—</u>
6) Total (of all facilities) @ Maximum High Water	<u>—</u>
7) Maximum Known Flood	<u>UNKNOWN</u>
8) At Time of Inspection	<u>UNKNOWN</u>



CREST:

ELEVATION: 660 ±Type: EarthWidth: Varies 25' to 50' Length: 190 FT.Spillover Uncontrolled concrete weirLocation about 25' from Right abutment

SPILLWAY:

SERVICE

AUXILIARY - None657

Elevation

Sharp crested - concrete

Type

6"

Width

✓ Type of Control

Uncontrolled

Controlled:

Type

(Flashboards; gate)

Number

Size/Length

Invert Material

Anticipated Length  
of operating service6' - Sloping

Chute Length

8' ±Height Between Spillway Crest  
& Approach Channel Invert  
(Weir Flow)

HYDROMETEROLOGICAL GAGES:

None used

Type : \_\_\_\_\_

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

FLOOD WATER CONTROL SYSTEM:

Warning System: \_\_\_\_\_ None

Method of Controlled Releases (mechanisms):  
\_\_\_\_\_  
\_\_\_\_\_

DRAINAGE AREA: 2.7 sq. miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: approx 60% urban-suburban & 40% woods & pastures

Terrain - Relief: hilly with relatively steep slopes

Surface - Soil: glacial till

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

none observed

Potential Sedimentation problem areas (natural or man-made; present or future)

None in vicinity of lake observed

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

None

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: \_\_\_\_\_

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool 0.8 (Miles)

Length of Shoreline (@ Spillway Crest) 5.68 (Miles)

# TAMS

Job No. 1579-17

Project LAKE MAHOPAC DAM INSPECTION

Subject HYDROLOGIC / HYDRAULIC COMPUTATIONS

Sheet 1 of     

Date MAY 27, 81

By DLC

Ch'k. by     

SUB AREA A

$$L = 3.5'' = 7000' = 1.3 \text{ mi.}$$

$$L_{CA} = 1.1'' = 2200' = 0.42 \text{ mi}$$

$$t_p = C_r (LL_{CA})^{0.3} \quad \text{use } C_r = 2$$

$$t_p = 2.0 (1.3 \times 0.42)^{0.3} = 1.67 \text{ hours}$$

$$t_R = t_p / 5.5 = 0.30 \text{ hrs.}$$

$$\text{for } t_R = 0.5 \text{ hours}$$

$$t_{PR} = t_p + 0.25(t_R - t_R) = 1.67 + 0.25(0.5 - 0.3) \\ = 1.67 + 0.05 = 1.72 \text{ hours}$$

$$\text{USE } 640 C_p = 400 \quad C_p = 0.625$$

SUB AREA B

$$L = 1.5 = 3000' = 0.57 \text{ mi}$$

$$L_{CA} = 0.5 = 1000' = 0.19 \text{ mi}$$

$$t_p = C_r (LL_{CA})^{0.3} \quad \text{use } C_r = 2$$

$$t_p = 2 (0.57 \times 0.19)^{0.3} = 1.03 \text{ hours}$$

$$t_R = t_p / 5.5 = 1.03 / 5.5 = 0.19$$

$$\text{for } t_R = 0.5$$

$$t_{PR} = t_p + 0.25(0.5 - 0.19) = 1.03 + 0.08 \\ = 1.11 \text{ hrs.}$$

$$\text{USE } 640 C_p = 400 \quad C_p = 0.625$$

# TAMS

Job No. 1579-17

Project LAKE MAHOPAC DAM

Subject HYDROLOGIC / HYDRAULIC COMPUTATIONS

Sheet 2 of     

Date     

By     

Ch'k. by     

ALL SEASON 24 HR 200 SQ MILE PMP = 22 inches

DURATION (HR)      6      12      24      48

% RAINFALL      112      123      133      141

INITIAL RAINFALL LOSS

1.0 inch

CONSTANT RAINFALL LOSS

0.1 inch/hour

CROSS SECTION 1000 FT DOWN STREAM OF DAM

SLOPE 0.038 Ft/Ft.

DISTANCE

ELEVATION

1) 0 660

$n = 0.035$

2) 250 640

3) 317 620

4) 318 614

$n = 0.015$  (lined channel)

5) 323 614

6) 324 620

7) 580 640

$n = 0.035$

8) 700 660

# TAMS

Job No. 1579-17 Sheet 3 of         
 Project LAKE MAHOPAC DAM SAFETY INVESTIGATION Date MAY 27, 1981  
 Subject HYDROLOGIC / HYDRAULIC COMPUTATIONS. By D.L.C.  
 Ch'k. by       

## SPILLWAY RATING

Effective width 8.0'

Assume  $C = 2.6$

$CXL = 20.8$

EL	$h_e$	$Q = CLH^{1.5}$
657	0	0
658	1	20.8
660	3	108.1
665	8	470.6
670	13	974.9

## DAM LENGTH

190'

## TOP OF DAM EL

660' MSL

## Sub-area A

$$6.55 \text{ in}^2 = 601.5 \text{ acres} = 0.94 \text{ sq mi}$$

## Sub-area B

$$5.75 \text{ in}^2 = 528.0 \text{ acres} = 0.83 \text{ sq mi}$$

LAKE AREA PLUS ISLANDS = 6.62 sq mi = 607.9 acres

LAKE SURFACE AREA AT EL. 657 =  $(607.9 - 48.7) = 559.2 \text{ acres}$

LAKE SURFACE AREA AT EL. 660 =  $(665.3 - 39.95) = 625.3 \text{ acres}$

LAKE SURFACE AREA AT EL. 670 =  $(771.8 - 33.1) = 738.7 \text{ acres}$

# TAMS

Job No. 1579-17

Project LAKE MAHOPAC

Subject HYDROLOGIC / HYDRAULIC COMPUTATIONS

Sheet 4 of       

Date MAY 28, 81


By D.L.C

Ch'k. by       

EL	ΔH	AREA	MEAN AREA	ΔVOL	SURCHARGE STORAGE Ac. Ft	STORAGE CAPACITY
657		559.2			0	1300
658	1	580.8	370.	570	570	1870
660	2	625.3	603.	1206	1780	3080
665	5	682.	653.7	3268.	5040	6340
670	5	738.7	710.4	3552	8600	9900

- Area of Islands removed from surface area of lake for surcharge storage computations -
- no rainfall losses will be computed for the 48+ acres of Islands.

$$\% \text{ impervious} = 35\% \quad \text{i.e.} \quad \frac{\text{Lake Area}}{\text{Drainage area}} = \frac{608}{1728} \times 100$$





PLUG HYDROGRAPH PACKAGE (MEC-1)  
 SAFETY VERSION JULY 1975  
 LAST MODIFICATION 29 APR 80

LAKE MANOPAC DAM									
PHASE 1 SAFETY INSPECTION									
MEC 1 DB PMF ANALYSIS MAY 1981									
1579-17									
1	A1	100	0	30	0	0	0	0	0
2	A2	5	4	1	0.25				
3	A3	1	1	0.75	0.5				
4	B1	1	1	1	1				
5	B2	1	1	1	1				
6	B3	1	1	1	1				
7	B4	1	1	1	1				
8	B5	1	1	1	1				
9	B6	1	1	1	1				
10	B7	1	1	1	1				
11	B8	1	1	1	1				
12	B9	1	1	1	1				
13	B10	1	1	1	1				
14	B11	1	1	1	1				
15	B12	1	1	1	1				
16	B13	1	1	1	1				
17	B14	1	1	1	1				
18	B15	1	1	1	1				
19	B16	1	1	1	1				
20	B17	1	1	1	1				
21	B18	1	1	1	1				
22	B19	1	1	1	1				
23	B20	1	1	1	1				
24	B21	1	1	1	1				
25	B22	1	1	1	1				
26	B23	1	1	1	1				
27	B24	1	1	1	1				
28	B25	1	1	1	1				
29	B26	1	1	1	1				
30	B27	1	1	1	1				
31	B28	1	1	1	1				
32	B29	1	1	1	1				
33	B30	1	1	1	1				
34	B31	1	1	1	1				
35	B32	1	1	1	1				
36	B33	1	1	1	1				
37	B34	1	1	1	1				
38	B35	1	1	1	1				
39	B36	1	1	1	1				
40	B37	1	1	1	1				
41	B38	1	1	1	1				

\*\*\*\*\*  
 CLOS HYDROGRAPH PACKAGE (HEC-1)  
 DAY SAFETY VERSION JULY 1978  
 LAST MODIFICATION CT APR 70  
 \*\*\*\*\*

RUN DATE= 5/10/78  
 TIME= 13.243

LAKE MAHOPAC DAM 1579-17  
 PHASE 1 SAFETY INSPECTION  
 HEC 1 DB PMF ANALYSIS MAY 1981

JOB SPECIFICATION  
 NO NMR NMIN IDAY INR ININ METRC IPLY IPRT NSTAN  
 100 0 30 0 0 0 0 0 0 0  
 JUPER 5 LROPT TRACE  
 0 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NPLAN= 1 NRTIO= 4 LRTIO= 1  
 RTIOS= 1.00 .75 .50 .25

SUB-AREA RUNOFF COMPUTATION

1 SUB-AREA A RUNOFF

ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUO  
 1 0 0 0 0 0 1 0 0  
 INYDG IUNG TAREA SHAP TRSDA TRSPC RATIO ISNCH ISAME LOCAL  
 1 1 1.40 0.00 0.00 2.70 0.00 0.000 0 1 1 0

PRECIP DATA

SPFE PPS R6 R2 R24 R48 R72 R96  
 0.00 22.00 112.00 123.00 133.00 141.00 0.00 0.00

TRSPC COMPUTED BY THE PROGRAM IS .600

LOSS DATA

LROPT STARR DLTKR RTIOL ERAIN STRKS RTIOX STRTL NSTL ALSMX RTIPP  
 0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .10 0.00 .51

UNIT HYDROGRAPH DATA  
 TP= 1.72 CP= .63 NTA= 0

RECESSION DATA

STRTO= -1.00 ORCSU= -.10 RTIOR= 1.50  
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SYNTER CP AND TP ARE TC= 3.98 AND P= 3.19 INTERVALS

UNIT HYDROGRAPH 19 END-OF-PERIOD ORDINATES, LAG= 1.72 HOURS, CP= .63 VOL= 1.00  
 44. 155. 272. 320. 276. 201. 146. 107. 78. 57.  
 41. 30. 22. 16. 12. 8. 6. 5. 3.

UNIT HYDROGRAPH DATA

TP= 1.72 CP= .63 NTA= 0

RECESSION DATA

START= -1.00 GRCSN= -10 RTIOR= 1.50

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 3.98 ND R= 3.19 INTERVALS

UNIT HYDROGRAPH TO END-OF-PERIOD ORIGINATES, LAG= 1.72 HOURS, CP= .63 VOL= 1.00  
44. 155. 272. 320. 276. 201. 146. 107. 78. 57.  
41. 30. 22. 16. 12. 8. 6. 3. 5. 3.

NO. DA	HR. MIN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW	NO. DA	HR. MIN	PERIOD	RAIN	EXCS	LOSS	COMP Q			
1.01	1.30	1	0.00	0.00	0.00	1.02	1.02	1.30	51	0.06	0.03	0.02	21.			
1.01	1.00	2	0.00	0.00	0.00	1.02	2.00	2.00	52	0.06	0.03	0.02	30.			
1.01	1.30	3	0.00	0.00	0.00	1.02	3.00	3.30	53	0.06	0.03	0.02	39.			
1.01	2.00	4	0.00	0.00	0.00	1.02	3.00	3.00	54	0.06	0.03	0.02	45.			
1.01	2.30	5	0.00	0.00	0.00	1.02	3.30	3.55	55	0.06	0.03	0.02	49.			
1.01	3.00	6	0.00	0.00	0.00	1.02	4.00	4.00	56	0.06	0.03	0.02	53.			
1.01	3.30	7	0.00	0.00	0.00	1.02	4.30	4.30	57	0.06	0.03	0.02	55.			
1.01	4.00	8	0.00	0.00	0.00	1.02	5.00	5.00	58	0.06	0.03	0.02	57.			
1.01	4.30	9	0.00	0.00	0.00	1.02	5.30	5.30	59	0.06	0.03	0.02	58.			
1.01	5.00	10	0.00	0.00	0.00	1.02	6.00	6.00	60	0.06	0.03	0.02	59.			
1.01	5.30	11	0.00	0.00	0.00	1.02	6.30	6.30	61	0.16	0.14	0.02	64.			
1.01	6.00	12	0.00	0.00	0.00	1.02	7.00	7.00	62	0.16	0.14	0.02	81.			
1.01	6.30	13	0.01	0.00	0.00	1.02	7.30	7.30	63	0.16	0.14	0.02	109.			
1.01	7.00	14	0.01	0.00	0.00	1.02	8.00	8.00	64	0.16	0.14	0.02	142.			
1.01	7.30	15	0.01	0.00	0.00	1.02	8.30	8.30	65	0.16	0.14	0.02	171.			
1.01	8.00	16	0.01	0.00	0.00	1.02	9.00	9.00	66	0.16	0.14	0.02	191.			
1.01	8.30	17	0.01	0.00	0.00	1.02	9.30	9.30	67	0.16	0.14	0.02	207.			
1.01	9.00	18	0.01	0.00	0.00	1.02	10.00	10.00	68	0.16	0.14	0.02	217.			
1.01	9.30	19	0.01	0.00	0.00	1.02	10.30	10.30	69	0.16	0.14	0.02	225.			
1.01	10.00	20	0.01	0.00	0.00	1.02	11.00	11.00	70	0.16	0.14	0.02	231.			
1.01	10.30	21	0.01	0.00	0.00	1.02	11.30	11.30	71	0.16	0.14	0.02	236.			
1.01	11.00	22	0.01	0.00	0.00	1.02	12.00	12.00	72	0.16	0.14	0.02	239.			
1.01	11.30	23	0.01	0.00	0.00	1.02	12.30	12.30	73	0.59	0.56	0.02	277.			
1.01	12.00	24	0.01	0.00	0.00	1.02	13.00	13.00	74	0.59	0.56	0.02	406.			
1.01	12.30	25	0.06	0.03	0.03	1.02	13.30	13.30	75	1.18	1.16	0.02	640.			
1.01	13.00	26	0.06	0.03	0.03	1.02	14.00	14.00	76	1.18	1.16	0.02	935.			
1.01	13.30	27	0.07	0.04	0.03	1.02	14.30	14.30	77	1.48	1.45	0.02	1229.			
1.01	14.00	28	0.07	0.04	0.03	1.02	15.00	15.00	78	1.48	1.45	0.02	1504.			
1.01	14.30	29	0.09	0.05	0.04	1.02	15.30	15.30	79	1.80	1.77	0.02	1773.			
1.01	15.00	30	0.09	0.05	0.04	1.02	16.00	16.00	80	5.69	5.67	0.02	2215.			
1.01	15.30	31	0.11	0.06	0.05	1.02	16.30	16.30	81	1.38	1.36	0.02	2891.			
1.01	16.00	32	0.34	0.19	0.15	1.02	17.00	17.00	82	1.38	1.36	0.02	3511.			
1.01	16.30	33	0.08	0.06	0.02	1.02	17.30	17.30	83	1.08	1.06	0.02	3752.			
1.01	17.00	34	0.08	0.06	0.02	1.02	18.00	18.00	84	1.08	1.06	0.02	3832.			
1.01	17.30	35	0.07	0.04	0.02	1.02	18.30	18.30	85	0.09	0.06	0.02	3078.			
1.01	18.00	36	0.07	0.04	0.02	1.02	19.00	19.00	86	0.09	0.06	0.02	2623.			
1.01	18.30	37	0.01	0.00	0.00	1.02	19.30	19.30	87	0.09	0.06	0.02	2106.			
1.01	19.00	38	0.01	0.00	0.00	1.02	20.00	20.00	88	0.09	0.06	0.02	1608.			
1.01	19.30	39	0.01	0.00	0.00	1.02	20.30	20.30	89	0.09	0.06	0.02	1203.			
1.01	20.00	40	0.01	0.00	0.00	1.02	21.00	21.00	90	0.09	0.06	0.02	907.			
1.01	20.30	41	0.01	0.00	0.00	1.02	21.30	21.30	91	0.09	0.06	0.02	692.			
1.01	21.00	42	0.01	0.00	0.00	1.02	22.00	22.00	92	0.09	0.06	0.02	533.			
1.01	21.30	43	0.01	0.00	0.00	1.02	22.30	22.30	93	0.09	0.06	0.02	417.			
1.01	22.00	44	0.01	0.00	0.00	1.02	23.00	23.00	94	0.09	0.06	0.02	368.			
1.01	22.30	45	0.01	0.00	0.00	1.02	23.30	23.30	95	0.09	0.06	0.02	353.			
1.01	23.00	46	0.01	0.00	0.00	1.03	0.00	0.00	96	0.09	0.06	0.02	359.			
1.01	23.30	47	0.01	0.00	0.00	1.03	0.30	0.30	97	0.00	0.00	0.00	326.			
1.01	0.00	48	0.01	0.00	0.00	1.03	1.00	1.00	98	0.00	0.00	0.00	313.			
1.02	0.30	49	0.06	0.03	0.02	1.03	1.30	1.30	99	0.00	0.00	0.00	300.			
1.02	1.00	50	0.06	0.03	0.02	1.03	2.00	2.00	100	0.00	0.00	0.00	288.			
SUM													24.82	23.02	1.80	42156.
													( 630. )	( 585. )	( 46. )	( 1193.72 )

1.01	2.30	46	.01	.00	1.02	23.30	95	.09	.06	.02	342.
1.02	2.30	47	.01	.00	1.03	23.30	95	.09	.06	.02	342.
1.03	2.30	48	.01	.00	1.03	23.30	95	.09	.06	.02	342.
1.04	2.30	49	.06	.03	1.03	23.30	95	.09	.06	.02	342.
1.05	2.30	50	.06	.03	1.03	23.30	95	.09	.06	.02	342.
SUM 24.82 23.02 1.80 42156.											
( 630.)( 385.)( 46.)( 1193.72)											

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

72-HOUR 420.  
TOTAL VOLUME 42015.

24-HOUR 845.  
THOUS CU P 1520.

6-HOUR 2486.  
THOUS CU P 1520.

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 1

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
1.01	1.02	1.03	1.04	1.05	1.06	1.07	1.08	1.09	1.10	1.11	1.12	1.13	1.14	1.15	1.16	1.17	1.18	1.19	1.20	1.21	1.22	1.23	1.24	1.25	1.26	1.27	1.28	1.29	1.30	1.31	1.32	1.33	1.34	1.35	1.36	1.37	1.38	1.39	1.40	1.41	1.42	1.43	1.44	1.45	1.46	1.47	1.48	1.49	1.50	1.51	1.52	1.53	1.54	1.55	1.56	1.57	1.58	1.59	1.60	1.61	1.62	1.63	1.64	1.65	1.66	1.67	1.68	1.69	1.70	1.71	1.72	1.73	1.74	1.75	1.76	1.77	1.78	1.79	1.80	1.81	1.82	1.83	1.84	1.85	1.86	1.87	1.88	1.89	1.90	1.91	1.92	1.93	1.94	1.95	1.96	1.97	1.98	1.99	2.00

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

72-HOUR 420.  
TOTAL VOLUME 42015.

24-HOUR 845.  
THOUS CU P 1520.

6-HOUR 2486.  
THOUS CU P 1520.

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 2

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
1.01	1.02	1.03	1.04	1.05	1.06	1.07	1.08	1.09	1.10	1.11	1.12	1.13	1.14	1.15	1.16	1.17	1.18	1.19	1.20	1.21	1.22	1.23	1.24	1.25	1.26	1.27	1.28	1.29	1.30	1.31	1.32	1.33	1.34	1.35	1.36	1.37	1.38	1.39	1.40	1.41	1.42	1.43	1.44	1.45	1.46	1.47	1.48	1.49	1.50	1.51	1.52	1.53	1.54	1.55	1.56	1.57	1.58	1.59	1.60	1.61	1.62	1.63	1.64	1.65	1.66	1.67	1.68	1.69	1.70	1.71	1.72	1.73	1.74	1.75	1.76	1.77	1.78	1.79	1.80	1.81	1.82	1.83	1.84	1.85	1.86	1.87	1.88	1.89	1.90	1.91	1.92	1.93	1.94	1.95	1.96	1.97	1.98	1.99	2.00

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

72-HOUR 420.  
TOTAL VOLUME 42015.

24-HOUR 845.  
THOUS CU P 1520.

6-HOUR 2486.  
THOUS CU P 1520.

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 3

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
1.01	1.02	1.03	1.04	1.05	1.06	1.07	1.08	1.09	1.10	1.11	1.12	1.13	1.14	1.15	1.16	1.17	1.18	1.19	1.20	1.21	1.22	1.23	1.24	1.25	1.26	1.27	1.28	1.29	1.30	1.31	1.32	1.33	1.34	1.35	1.36	1.37	1.38	1.39	1.40	1.41	1.42	1.43	1.44	1.45	1.46	1.47	1.48	1.49	1.50	1.51	1.52	1.53	1.54	1.55	1.56	1.57	1.58	1.59	1.60	1.61	1.62	1.63	1.64	1.65	1.66	1.67	1.68	1.69	1.70	1.71	1.72	1.73	1.74	1.75	1.76	1.77	1.78	1.79	1.80	1.81	1.82	1.83	1.84	1.85	1.86	1.87	1.88	1.89	1.90	1.91	1.92	1.93	1.94	1.95	1.96	1.97	1.98	1.99	2.00

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

72-HOUR 420.  
TOTAL VOLUME 42015.

24-HOUR 845.  
THOUS CU P 1520.

6-HOUR 2486.  
THOUS CU P 1520.

PEAK 3752.  
CFS 2486.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

INCHES 106.  
AC-FT 1520.  
THOUS CU P 1520.

113. 276. 765. 754. 1280. 902. 490.  
 244. 22. 2.  
 1206. 234.  
 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 2814. 1864. 633. 315. 31512.  
 53. 18. 9. 892.  
 INCHES 12.39 16.84 17.45 17.45  
 314.65 427.62 443.19 443.19  
 924. 1256. 1302. 1302.  
 1140. 1550. 1606. 1606.  
 AC-FT  
 THOUS CU M

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 3									
1.	1.	2.	2.	2.	2.	2.	2.	2.	2.
2.	2.	3.	3.	4.	4.	4.	4.	4.	4.
3.	5.	5.	7.	7.	15.	15.	20.	20.	24.
35.	47.	59.	65.	63.	57.	49.	39.	39.	30.
17.	13.	10.	8.	7.	6.	6.	6.	7.	7.
15.	19.	22.	25.	26.	28.	29.	29.	30.	30.
32.	40.	55.	71.	85.	96.	109.	113.	113.	116.

HYDROGRAPH DATA  
 INLET TAREA SNAP TRSDA TRSPT RATIO %SNOW TIME L  
 1 1 1 2 0.0 1.000 0 0  
 PRECIP DATA  
 SPTS PMS R6 R12 R24 R48 R72 R96  
 0.00 22.00 112.00 123.00 133.00 141.00 0.00 0.00  
 TEST COMPUTED BY THE PROGRAM IS .800

LOSS DATA  
 LEQPT STRKR PLTR RTIOL ERATN STRKS RTIOK STRTL CNSTL ALSMX RTIMP  
 0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 0.10 0.00 .57

UNIT HYDROGRAPH DATA  
 TP= 1.11 CP= .63 NTA= 0

RECESSION DATA  
 STRKR= -1.00 GRCSN= -1.10 RTIOR= 1.50  
 APPROXIMATE CLASS COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 2.63 AND R= 1.91 INTERVALS

UNIT HYDROGRAPH 12 END-OF-PERIOD ORDINATES, LAG= 1.11 HOURS, CP= .63 VOL= 1.00  
 112. 350. 461. 188. 110. 64. 22. 13.

NO. OF PERIODS	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW	NO. OF PERIODS	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW
1	1	0.00	0.00	0.00	1.02	1	1	0.00	0.00	0.00	1.02
2	2	0.00	0.00	0.00	1.02	2	2	0.00	0.00	0.00	1.02
3	3	0.00	0.00	0.00	1.02	3	3	0.00	0.00	0.00	1.02
4	4	0.00	0.00	0.00	1.02	4	4	0.00	0.00	0.00	1.02
5	5	0.00	0.00	0.00	1.02	5	5	0.00	0.00	0.00	1.02
6	6	0.00	0.00	0.00	1.02	6	6	0.00	0.00	0.00	1.02
7	7	0.00	0.00	0.00	1.02	7	7	0.00	0.00	0.00	1.02
8	8	0.00	0.00	0.00	1.02	8	8	0.00	0.00	0.00	1.02
9	9	0.00	0.00	0.00	1.02	9	9	0.00	0.00	0.00	1.02
10	10	0.00	0.00	0.00	1.02	10	10	0.00	0.00	0.00	1.02
11	11	0.00	0.00	0.00	1.02	11	11	0.00	0.00	0.00	1.02
12	12	0.00	0.00	0.00	1.02	12	12	0.00	0.00	0.00	1.02
13	13	0.00	0.00	0.00	1.02	13	13	0.00	0.00	0.00	1.02
14	14	0.00	0.00	0.00	1.02	14	14	0.00	0.00	0.00	1.02
15	15	0.00	0.00	0.00	1.02	15	15	0.00	0.00	0.00	1.02
16	16	0.00	0.00	0.00	1.02	16	16	0.00	0.00	0.00	1.02
17	17	0.00	0.00	0.00	1.02	17	17	0.00	0.00	0.00	1.02
18	18	0.00	0.00	0.00	1.02	18	18	0.00	0.00	0.00	1.02
19	19	0.00	0.00	0.00	1.02	19	19	0.00	0.00	0.00	1.02
20	20	0.00	0.00	0.00	1.02	20	20	0.00	0.00	0.00	1.02
21	21	0.00	0.00	0.00	1.02	21	21	0.00	0.00	0.00	1.02
22	22	0.00	0.00	0.00	1.02	22	22	0.00	0.00	0.00	1.02
23	23	0.00	0.00	0.00	1.02	23	23	0.00	0.00	0.00	1.02
24	24	0.00	0.00	0.00	1.02	24	24	0.00	0.00	0.00	1.02
25	25	0.00	0.00	0.00	1.02	25	25	0.00	0.00	0.00	1.02
26	26	0.00	0.00	0.00	1.02	26	26	0.00	0.00	0.00	1.02
27	27	0.00	0.00	0.00	1.02	27	27	0.00	0.00	0.00	1.02
28	28	0.00	0.00	0.00	1.02	28	28	0.00	0.00	0.00	1.02
29	29	0.00	0.00	0.00	1.02	29	29	0.00	0.00	0.00	1.02
30	30	0.00	0.00	0.00	1.02	30	30	0.00	0.00	0.00	1.02
31	31	0.00	0.00	0.00	1.02	31	31	0.00	0.00	0.00	1.02
32	32	0.00	0.00	0.00	1.02	32	32	0.00	0.00	0.00	1.02
33	33	0.00	0.00	0.00	1.02	33	33	0.00	0.00	0.00	1.02
34	34	0.00	0.00	0.00	1.02	34	34	0.00	0.00	0.00	1.02
35	35	0.00	0.00	0.00	1.02	35	35	0.00	0.00	0.00	1.02
36	36	0.00	0.00	0.00	1.02	36	36	0.00	0.00	0.00	1.02
37	37	0.00	0.00	0.00	1.02	37	37	0.00	0.00	0.00	1.02
38	38	0.00	0.00	0.00	1.02	38	38	0.00	0.00	0.00	1.02
39	39	0.00	0.00	0.00	1.02	39	39	0.00	0.00	0.00	1.02
40	40	0.00	0.00	0.00	1.02	40	40	0.00	0.00	0.00	1.02
41	41	0.00	0.00	0.00	1.02	41	41	0.00	0.00	0.00	1.02
42	42	0.00	0.00	0.00	1.02	42	42	0.00	0.00	0.00	1.02
43	43	0.00	0.00	0.00	1.02	43	43	0.00	0.00	0.00	1.02
44	44	0.00	0.00	0.00	1.02	44	44	0.00	0.00	0.00	1.02
45	45	0.00	0.00	0.00	1.02	45	45	0.00	0.00	0.00	1.02
46	46	0.00	0.00	0.00	1.02	46	46	0.00	0.00	0.00	1.02



55. 42. 110. 141. 155. 164. 169. 172. 175. 176.  
 175. 187. 217. 244. 255. 264. 274. 280. 292. 311.  
 266. 321. 211. 244. 255. 264. 274. 280. 292. 311.  
 292. 275. 266. 255. 244. 234. 225. 216. 207.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 CFS 3215 1865 616 308 30280  
 CFS 91 53 17 9 272  
 INCHES 13.34 17.64 19.35 19.35  
 336.96 448.12 466.19 466.19  
 AC-FT 925 1223 1272 1272  
 THOUS CU M 1141 1508 1569 1569

HYDROGRAPH AT STA 2 FOR PLAN 1, RTIO 3

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 CFS 2423 1243 411 205 20220  
 CFS 61 33 12 6 581  
 INCHES 8.90 11.76 12.24 12.24  
 225.97 298.75 310.79 310.79  
 AC-FT 617 815 848 848  
 THOUS CU M 760 1005 1046 1046

HYDROGRAPH AT STA 2 FOR PLAN 1, RTIO 4

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.
1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.	33.	34.	35.	36.	37.	38.	39.	40.	41.	42.	43.	44.	45.	46.	47.	48.	49.	50.	51.	52.	53.	54.	55.	56.	57.	58.	59.	60.	61.	62.	63.	64.	65.	66.	67.	68.	69.	70.	71.	72.	73.	74.	75.	76.	77.	78.	79.	80.	81.	82.	83.	84.	85.	86.	87.	88.	89.	90.	91.	92.	93.	94.	95.	96.	97.	98.	99.	100.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 CFS 1072 622 205 103 13260  
 CFS 30 18 6 3 291  
 INCHES 4.45 5.88 6.12 6.12  
 112.99 149.37 155.40 155.40  
 AC-FT 308 408 424 424  
 THOUS CU M 380 503 523 523

COMBINE HYDROGRAPHS

3 COMBINE TWO HYDROGRAPHS

ISTAG ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO  
 3 2 0 0 0 0 1 0 0

SUM OF 2 HYDROGRAPHS AT 7. 3 PLAN 1 RTIO 1 P. A. 8.



ISTAG	ICOMP	I ECON	ITAPE	JPLY	JPRY	INAME	ISTAGE	IAUTO
3	2	0	0	0	0	1	0	0

SUM OF 2 HYDROGRAPHS AT		3 PLAN 1 RTIO 1	
3.	5.	7.	8.
4.	6.	7.	8.

2	8	10	15	16	17	18
10	9	19	23	37	78	98
13	236	281	276	211	169	116
64	42	35	17	26	125	89
51	77	102	108	117	119	54
199	264	350	378	446	420	121
432	722	1021	1410	2328	451	464
757	1244	1640	2289	3370	3690	5053
1390	2444	3364	4364	5320	6329	7322
2390	3764	5220	6664	8168	9612	11058
3990	5915	7920	9964	11938	13912	15885

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CS	7797	492	1668	83	8355	8355
INCHS	221	138	41	2	252	252
INCHS		16.97	22.37	23.85	23.85	23.85
INCHS		430.62	563.62	605.68	605.68	605.68
AC-T		2442	3303	333	3432	3432
INCHS CU M		3012	4071	4233	4233	4233

SUM OF 2 HYDROGRAPHS AT ... 3 PLAN 1 RTIO 2

2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
16.	16.	16.	16.	16.	16.	16.	16.	16.	16.	16.	16.	16.
9.	12.	14.	17.	20.	23.	26.	29.	32.	35.	38.	41.	44.
45.	48.	51.	54.	57.	60.	63.	66.	69.	72.	75.	78.	81.
104.	113.	122.	131.	140.	149.	158.	167.	176.	185.	194.	203.	212.
352.	364.	376.	388.	400.	412.	424.	436.	448.	460.	472.	484.	496.
1114.	1146.	1178.	1210.	1242.	1274.	1306.	1338.	1370.	1402.	1434.	1466.	1498.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL
CSS	5840.	3695.	1250.	625.	6220.
CSS	160.	105.	35.	15.	1704.
INCHES		12.72	17.82	17.88	17.88
AC-CU	323.19	437.49	454.26	454.26	454.26
INCHES	1831.	2475.	2574.	2574.	2574.
CU M	2259.	3058.	3175.	3175.	3175.

SUM OF 2 HYDROGRAPHS AT 3 PLAN 1 RTIO 3

	1-	2-	3-	4-	5-	6-HOUR	PEAK	CFR	INCHES	72-HOUR	TOTAL VOLUME
1-	1-	2-	3-	4-	5-	6-HOUR <td>PEAK<td>CFR<td>INCHES<td>72-HOUR<td>TOTAL VOLUME</td></td></td></td></td>	PEAK <td>CFR<td>INCHES<td>72-HOUR<td>TOTAL VOLUME</td></td></td></td>	CFR <td>INCHES<td>72-HOUR<td>TOTAL VOLUME</td></td></td>	INCHES <td>72-HOUR<td>TOTAL VOLUME</td></td>	72-HOUR <td>TOTAL VOLUME</td>	TOTAL VOLUME
4-	4-	4-	5-	6-	7-	8-	9-	10-	11-	12-	13-
8-	8-	9-	10-	11-	12-	13-	14-	15-	16-	17-	18-
12-	12-	13-	14-	15-	16-	17-	18-	19-	20-	21-	22-
16-	16-	17-	18-	19-	20-	21-	22-	23-	24-	25-	26-
20-	20-	21-	22-	23-	24-	25-	26-	27-	28-	29-	30-
24-	24-	25-	26-	27-	28-	29-	30-	31-	32-	33-	34-
28-	28-	29-	30-	31-	32-	33-	34-	35-	36-	37-	38-
32-	32-	33-	34-	35-	36-	37-	38-	39-	40-	41-	42-
36-	36-	37-	38-	39-	40-	41-	42-	43-	44-	45-	46-
40-	40-	41-	42-	43-	44-	45-	46-	47-	48-	49-	50-
44-	44-	45-	46-	47-	48-	49-	50-	51-	52-	53-	54-
48-	48-	49-	50-	51-	52-	53-	54-	55-	56-	57-	58-
52-	52-	53-	54-	55-	56-	57-	58-	59-	60-	61-	62-
56-	56-	57-	58-	59-	60-	61-	62-	63-	64-	65-	66-
60-	60-	61-	62-	63-	64-	65-	66-	67-	68-	69-	70-
64-	64-	65-	66-	67-	68-	69-	70-	71-	72-	73-	74-
68-	68-	69-	70-	71-	72-	73-	74-	75-	76-	77-	78-
72-	72-	73-	74-	75-	76-	77-	78-	79-	80-	81-	82-
76-	76-	77-	78-	79-	80-	81-	82-	83-	84-	85-	86-
80-	80-	81-	82-	83-	84-	85-	86-	87-	88-	89-	90-
84-	84-	85-	86-	87-	88-	89-	90-	91-	92-	93-	94-
88-	88-	89-	90-	91-	92-	93-	94-	95-	96-	97-	98-
92-	92-	93-	94-	95-	96-	97-	98-	99-	100-	101-	102-
96-	96-	97-	98-	99-	100-	101-	102-	103-	104-	105-	106-
100-	100-	101-	102-	103-	104-	105-	106-	107-	108-	109-	110-
104-	104-	105-	106-	107-	108-	109-	110-	111-	112-	113-	114-
108-	108-	109-	110-	111-	112-	113-	114-	115-	116-	117-	118-
112-	112-	113-	114-	115-	116-	117-	118-	119-	120-	121-	122-
116-	116-	117-	118-	119-	120-	121-	122-	123-	124-	125-	126-
120-	120-	121-	122-	123-	124-	125-	126-	127-	128-	129-	130-
124-	124-	125-	126-	127-	128-	129-	130-	131-	132-	133-	134-
128-	128-	129-	130-	131-	132-	133-	134-	135-	136-	137-	138-
132-	132-	133-	134-	135-	136-	137-	138-	139-	140-	141-	142-
136-	136-	137-	138-	139-	140-	141-	142-	143-	144-	145-	146-
140-	140-	141-	142-	143-	144-	145-	146-	147-	148-	149-	150-
144-	144-	145-	146-	147-	148-	149-	150-	151-	152-	153-	154-
148-	148-	149-	150-	151-	152-	153-	154-	155-	156-	157-	158-
152-	152-	153-	154-	155-	156-	157-	158-	159-	160-	161-	162-
156-	156-	157-	158-	159-	160-	161-	162-	163-	164-	165-	166-
160-	160-	161-	162-	163-	164-	165-	166-	167-	168-	169-	170-
164-	164-	165-	166-	167-	168-	169-	170-	171-	172-	173-	174-
168-											

22. 39. 95. 301. 372. 392. 458.  
 23. 39. 95. 301. 372. 392. 458.  
 24. 39. 95. 301. 372. 392. 458.  
 25. 39. 95. 301. 372. 392. 458.  
 26. 39. 95. 301. 372. 392. 458.  
 27. 39. 95. 301. 372. 392. 458.  
 28. 39. 95. 301. 372. 392. 458.  
 29. 39. 95. 301. 372. 392. 458.  
 30. 39. 95. 301. 372. 392. 458.  
 31. 39. 95. 301. 372. 392. 458.  
 32. 39. 95. 301. 372. 392. 458.  
 33. 39. 95. 301. 372. 392. 458.  
 34. 39. 95. 301. 372. 392. 458.  
 35. 39. 95. 301. 372. 392. 458.  
 36. 39. 95. 301. 372. 392. 458.  
 37. 39. 95. 301. 372. 392. 458.  
 38. 39. 95. 301. 372. 392. 458.  
 39. 39. 95. 301. 372. 392. 458.  
 40. 39. 95. 301. 372. 392. 458.  
 41. 39. 95. 301. 372. 392. 458.  
 42. 39. 95. 301. 372. 392. 458.  
 43. 39. 95. 301. 372. 392. 458.  
 44. 39. 95. 301. 372. 392. 458.  
 45. 39. 95. 301. 372. 392. 458.  
 46. 39. 95. 301. 372. 392. 458.  
 47. 39. 95. 301. 372. 392. 458.  
 48. 39. 95. 301. 372. 392. 458.  
 49. 39. 95. 301. 372. 392. 458.  
 50. 39. 95. 301. 372. 392. 458.  
 51. 39. 95. 301. 372. 392. 458.  
 52. 39. 95. 301. 372. 392. 458.  
 53. 39. 95. 301. 372. 392. 458.  
 54. 39. 95. 301. 372. 392. 458.  
 55. 39. 95. 301. 372. 392. 458.  
 56. 39. 95. 301. 372. 392. 458.  
 57. 39. 95. 301. 372. 392. 458.  
 58. 39. 95. 301. 372. 392. 458.  
 59. 39. 95. 301. 372. 392. 458.  
 60. 39. 95. 301. 372. 392. 458.  
 61. 39. 95. 301. 372. 392. 458.  
 62. 39. 95. 301. 372. 392. 458.  
 63. 39. 95. 301. 372. 392. 458.  
 64. 39. 95. 301. 372. 392. 458.  
 65. 39. 95. 301. 372. 392. 458.  
 66. 39. 95. 301. 372. 392. 458.  
 67. 39. 95. 301. 372. 392. 458.  
 68. 39. 95. 301. 372. 392. 458.  
 69. 39. 95. 301. 372. 392. 458.  
 70. 39. 95. 301. 372. 392. 458.  
 71. 39. 95. 301. 372. 392. 458.  
 72. 39. 95. 301. 372. 392. 458.  
 73. 39. 95. 301. 372. 392. 458.  
 74. 39. 95. 301. 372. 392. 458.  
 75. 39. 95. 301. 372. 392. 458.  
 76. 39. 95. 301. 372. 392. 458.  
 77. 39. 95. 301. 372. 392. 458.  
 78. 39. 95. 301. 372. 392. 458.  
 79. 39. 95. 301. 372. 392. 458.  
 80. 39. 95. 301. 372. 392. 458.  
 81. 39. 95. 301. 372. 392. 458.  
 82. 39. 95. 301. 372. 392. 458.  
 83. 39. 95. 301. 372. 392. 458.  
 84. 39. 95. 301. 372. 392. 458.  
 85. 39. 95. 301. 372. 392. 458.  
 86. 39. 95. 301. 372. 392. 458.  
 87. 39. 95. 301. 372. 392. 458.  
 88. 39. 95. 301. 372. 392. 458.  
 89. 39. 95. 301. 372. 392. 458.  
 90. 39. 95. 301. 372. 392. 458.  
 91. 39. 95. 301. 372. 392. 458.  
 92. 39. 95. 301. 372. 392. 458.  
 93. 39. 95. 301. 372. 392. 458.  
 94. 39. 95. 301. 372. 392. 458.  
 95. 39. 95. 301. 372. 392. 458.  
 96. 39. 95. 301. 372. 392. 458.  
 97. 39. 95. 301. 372. 392. 458.  
 98. 39. 95. 301. 372. 392. 458.  
 99. 39. 95. 301. 372. 392. 458.  
 100. 39. 95. 301. 372. 392. 458.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 389. 2462. 833. 415.  
 110. 70. 24. 12.  
 8.48 11.48 11.92 11.92

205.46 291.66 302.84 302.84  
 1221. 1633. 1716. 1716.  
 1506. 2039. 2117. 2117.

SUM OF 2 HYDROGRAPHS AT 3 PLAN 1 RTIO 4  
 1. 1. 2. 2. 2. 2. 2. 2.  
 2. 2. 3. 4. 4. 4. 4. 4.  
 3. 3. 5. 6. 6. 6. 6. 6.  
 4. 4. 6. 7. 7. 7. 7. 7.  
 5. 5. 8. 9. 9. 9. 9. 9.  
 6. 6. 10. 11. 11. 11. 11. 11.  
 7. 7. 12. 13. 13. 13. 13. 13.  
 8. 8. 14. 15. 15. 15. 15. 15.  
 9. 9. 16. 17. 17. 17. 17. 17.  
 10. 10. 18. 19. 19. 19. 19. 19.  
 11. 11. 20. 21. 21. 21. 21. 21.  
 12. 12. 22. 23. 23. 23. 23. 23.  
 13. 13. 24. 25. 25. 25. 25. 25.  
 14. 14. 26. 27. 27. 27. 27. 27.  
 15. 15. 28. 29. 29. 29. 29. 29.  
 16. 16. 30. 31. 31. 31. 31. 31.  
 17. 17. 32. 33. 33. 33. 33. 33.  
 18. 18. 34. 35. 35. 35. 35. 35.  
 19. 19. 36. 37. 37. 37. 37. 37.  
 20. 20. 38. 39. 39. 39. 39. 39.  
 21. 21. 40. 41. 41. 41. 41. 41.  
 22. 22. 42. 43. 43. 43. 43. 43.  
 23. 23. 44. 45. 45. 45. 45. 45.  
 24. 24. 46. 47. 47. 47. 47. 47.  
 25. 25. 48. 49. 49. 49. 49. 49.  
 26. 26. 50. 51. 51. 51. 51. 51.  
 27. 27. 52. 53. 53. 53. 53. 53.  
 28. 28. 54. 55. 55. 55. 55. 55.  
 29. 29. 56. 57. 57. 57. 57. 57.  
 30. 30. 58. 59. 59. 59. 59. 59.  
 31. 31. 60. 61. 61. 61. 61. 61.  
 32. 32. 62. 63. 63. 63. 63. 63.  
 33. 33. 64. 65. 65. 65. 65. 65.  
 34. 34. 66. 67. 67. 67. 67. 67.  
 35. 35. 68. 69. 69. 69. 69. 69.  
 36. 36. 70. 71. 71. 71. 71. 71.  
 37. 37. 72. 73. 73. 73. 73. 73.  
 38. 38. 74. 75. 75. 75. 75. 75.  
 39. 39. 76. 77. 77. 77. 77. 77.  
 40. 40. 78. 79. 79. 79. 79. 79.  
 41. 41. 80. 81. 81. 81. 81. 81.  
 42. 42. 82. 83. 83. 83. 83. 83.  
 43. 43. 84. 85. 85. 85. 85. 85.  
 44. 44. 86. 87. 87. 87. 87. 87.  
 45. 45. 88. 89. 89. 89. 89. 89.  
 46. 46. 90. 91. 91. 91. 91. 91.  
 47. 47. 92. 93. 93. 93. 93. 93.  
 48. 48. 94. 95. 95. 95. 95. 95.  
 49. 49. 96. 97. 97. 97. 97. 97.  
 50. 50. 98. 99. 99. 99. 99. 99.  
 51. 51. 100. 101. 101. 101. 101. 101.  
 52. 52. 102. 103. 103. 103. 103. 103.  
 53. 53. 104. 105. 105. 105. 105. 105.  
 54. 54. 106. 107. 107. 107. 107. 107.  
 55. 55. 108. 109. 109. 109. 109. 109.  
 56. 56. 110. 111. 111. 111. 111. 111.  
 57. 57. 112. 113. 113. 113. 113. 113.  
 58. 58. 114. 115. 115. 115. 115. 115.  
 59. 59. 116. 117. 117. 117. 117. 117.  
 60. 60. 118. 119. 119. 119. 119. 119.  
 61. 61. 120. 121. 121. 121. 121. 121.  
 62. 62. 122. 123. 123. 123. 123. 123.  
 63. 63. 124. 125. 125. 125. 125. 125.  
 64. 64. 126. 127. 127. 127. 127. 127.  
 65. 65. 128. 129. 129. 129. 129. 129.  
 66. 66. 130. 131. 131. 131. 131. 131.  
 67. 67. 132. 133. 133. 133. 133. 133.  
 68. 68. 134. 135. 135. 135. 135. 135.  
 69. 69. 136. 137. 137. 137. 137. 137.  
 70. 70. 138. 139. 139. 139. 139. 139.  
 71. 71. 140. 141. 141. 141. 141. 141.  
 72. 72. 142. 143. 143. 143. 143. 143.  
 73. 73. 144. 145. 145. 145. 145. 145.  
 74. 74. 146. 147. 147. 147. 147. 147.  
 75. 75. 148. 149. 149. 149. 149. 149.  
 76. 76. 150. 151. 151. 151. 151. 151.  
 77. 77. 152. 153. 153. 153. 153. 153.  
 78. 78. 154. 155. 155. 155. 155. 155.  
 79. 79. 156. 157. 157. 157. 157. 157.  
 80. 80. 158. 159. 159. 159. 159. 159.  
 81. 81. 160. 161. 161. 161. 161. 161.  
 82. 82. 162. 163. 163. 163. 163. 163.  
 83. 83. 164. 165. 165. 165. 165. 165.  
 84. 84. 166. 167. 167. 167. 167. 167.  
 85. 85. 168. 169. 169. 169. 169. 169.  
 86. 86. 170. 171. 171. 171. 171. 171.  
 87. 87. 172. 173. 173. 173. 173. 173.  
 88. 88. 174. 175. 175. 175. 175. 175.  
 89. 89. 176. 177. 177. 177. 177. 177.  
 90. 90. 178. 179. 179. 179. 179. 179.  
 91. 91. 180. 181. 181. 181. 181. 181.  
 92. 92. 182. 183. 183. 183. 183. 183.  
 93. 93. 184. 185. 185. 185. 185. 185.  
 94. 94. 186. 187. 187. 187. 187. 187.  
 95. 95. 188. 189. 189. 189. 189. 189.  
 96. 96. 190. 191. 191. 191. 191. 191.  
 97. 97. 192. 193. 193. 193. 193. 193.  
 98. 98. 194. 195. 195. 195. 195. 195.  
 99. 99. 196. 197. 197. 197. 197. 197.  
 100. 100. 198. 199. 199. 199. 199. 199.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 1940. 1231. 417. 208.  
 55. 35. 12. 6.  
 4.24 5.74 5.96 5.96  
 107.73 145.83 151.42 151.42  
 610. 826. 858. 858.  
 753. 1019. 1058. 1058.

4 ROUTE HYDROGRAPH THROUGH LAKE MAHCPAC  
 HYDROGRAPH ROUTING

ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO  
 4 1 0 0 0 0 1 0  
 GLOSS CLOSS AVG IRES ISAME IOPT IPMP LSTR  
 0.0 0.00 0.00 1 1 0 0 0  
 ASTPS NSTOL LAG AFSKK X TSK STORA ISPRAT  
 1 0 0 0.000 0.000 0.000 1300. -1

STAGE 657.00 658.00 660.00 665.00 670.00  
 FLOW 0.00 20.80 108.80 470.60 974.00  
 CAPACITY 1303. 1870. 3080. 6340. 9900.  
 ELEVATION 657. 658. 660. 665. 670.

CREL SPWID CROW EXPW ELEV COOL CAREA EXPL  
 657.0 0.0 0.0 0.0 0.0 0.0 0.0  
 TOPEL COOP EXPD DAMWID  
 640.0 3.1 1.5 193.



STATION 6, PLAN 1, RATIO 2  
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

SEE ATTACH IS 560. AT TIME 47.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	520.	520.	161.	78.	706.
CMS	15.	15.	5.	2.	221.
INCHES	1.70	2.22	2.24	2.24	2.24
AC-F.	45.54	56.45	56.85	56.85	56.85
THOUS CU FT	320.	320.	320.	320.	322.
	394.	394.	394.	394.	397.

STATION 4, PLAN 1, RATIO 3  
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

0000NNNN0  
0000NNNN0  
0000NNNN0  
0000NNNN0  
0000NNNN0  
OUTFLOW  
0000NNNN0  
0000NNNN0  
0000NNNN0  
0000NNNN0  
0000NNNN0

38.	30.	69.	76.	82.	85.	88.	90.
38.	30.	69.	76.	82.	85.	88.	90.
93.	94.	95.	96.	97.	98.	98.	99.
93.	94.	95.	96.	97.	98.	98.	99.

[illegible][illegible]

RECEIVED SUPPLIES - 99. AT 714E 50.00 HOURS

	PEAK SEC	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CBS	3.	94	36	18	1780.
CBS	3.	5	1	1	50.
INCHES		52	50	51	
PM		8.23	12.68	12.98	
AC-FT		47	72	74	
THOUS CU M		58	89	91	

STATION 4, PLAN 1, RAYNO 4

[illegible]



**THE UNIVERSITY OF CHICAGO**

04(1)	04(2)	04(3)	ELAVT	ELMAX	RLNTH	SFL
.0350	.0150	.0350	614.0	660.0	1000.	.03500

CCSS SECTION COMPILES--STA,LEV,STA,LEV--ETC

	C-00	-29	-61	1-01	-1-32	3-08	4-79	6-97	9-39	12-67
STAGE	16.26	20.39	29.00	43.55	64.04	90.44	120.63	153.52	188.49	226.15
CUTFLOW	27160.16	289.85	757.77	1390.03	2401.68	4003.80	6395.30	9752.42	14237.34	20001.96
		94723.95	43906.00	61903.31	91031.12	134250.26	196915.93	274237.33	366302.02	473362.98
STAGE	614.00	816.42	618.84	621.26	623.68	626.11	628.53	630.95	633.37	635.79
	635.21	640.63	643.05	645.47	647.89	650.32	652.74	655.16	657.58	660.00
FLOW	27160.16	289.85	757.77	1390.03	2401.68	4003.80	6395.30	9752.42	14237.34	20001.96
		36721.95	43906.00	61903.31	91031.12	134250.26	196915.93	274237.33	366302.02	473362.98

5. PLAN 1, RY20 1

**STATION**

**OUTFLOW**

[illegible]

**STOP**

STOR

## STAGE

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CIS	1371.	120.1	412.	194.	19837.
--- CIS	39.	36.	12.	6.	562.
14CMIS		4.35	5.67	5.70	5.70
PP		110.39	144.07	144.66	144.66





[illegible]





# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	657.00	657.00	660.00
STORAGE	1300.	1300.	3080.
OUTFLOW	0.	0.	100.

RATIO OF PPF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	661.57	1.57	4101.	1372.	9.00	45.00	0.00
.75	660.74	1.74	3865.	560.	8.00	47.00	0.00
.50	659.77	0.00	2942.	99.	0.00	50.00	0.00
.25	658.43	0.00	2129.	40.	0.00	50.00	0.00

PLAN 1		STATION 5	
RATIO	MAXIMUM FLOW-CFS	MAXIMUM STAGE-FT	TIME HOURS
1.00	1371.	621.2	45.00
.75	540.	617.7	47.50
.50	99.	616.8	50.00
.25	40.	616.3	50.00

## REFERENCES

## APPENDIX E

#### REFERENCES

1. "Flood Hydrograph Package (HEC-1) Users Manual for Dam Safety Investigations", U. S. Army Corps of Engineers, Hydrologic Engineering Center, September 1979.
2. "Seasonal Variation of the Probable Maximum Precipitation, East of the 105th Meridian for Areas from 10 to 1,000 Square Miles, and Durations of 6, 12, 24 and 48 Hours", Hydrometeorological Report No. 33. Weather Bureau, U.S. Department of Commerce, April 1956.
3. "Recommended Guidelines for Safety Inspection of Dams", Department of the Army, Office of the Chief of Engineers, Appendix B.
4. The University of the State of New York, The State Education Department State Museum and Science Service Geological Survey - MAP and Chart Series No. 5, Geologic MAP of New York 1961, Lower Hudson Sheet.

EN  
DATE  
ILME